

Standard Operating Procedure (SOP) for Resolving ALARM_8819 on Arista Access Switches

Node: Arista-Access-Chennai-TN-86 | **Vendor:** Arista | **Severity:** Critical | **Alarm Code:** ALARM_8819

Description

This SOP outlines the steps to diagnose and resolve the ALARM_8819, a critical alarm indicating a hardware failure or malfunction on the Arista Access Switch, Node ID: Arista-Access-Chennai-TN-86.

Potential Root Causes

Cause	Probability
Hardware Failure (e.g., fan, power supply, or interface module)	High
Software Bug or Configuration Issue	Medium
Environmental Factors (e.g., overheating, power fluctuations)	Low

Diagnostic Commands

```
show system resources
show environment
show power
show interface status
show platform
show version
```

Resolution Steps

- Step 1: {'Step': '1. Verify alarm status and gather more information', 'Action': "run 'show alarm' command to confirm the alarm and note the timestamp", 'CLI_Command': 'show alarm'}
- Step 2: {'Step': '2. Check system resources and environmental factors', 'Action': "run 'show system resources' and 'show environment' commands to check for any issues", 'CLI_Commands': ['show system resources', 'show environment']}
- Step 3: {'Step': '3. Inspect the hardware for any signs of failure or malfunction', 'Action': 'physically inspect the switch and its components for any signs of damage or malfunction', 'Note': 'this step requires physical access to the switch and its components'}
- Step 4: {'Step': '4. Check configuration and software for any issues', 'Action': "run 'show configuration' and 'show version' commands to check for any software or configuration issues", 'CLI_Commands': ['show configuration', 'show version']}

Step 5: {'Step': '5. Attempt to reset or reboot the switch (if possible)', 'Action': "run 'reload' or 'shutdown' command to attempt to reset or reboot the switch", 'CLI_Command': 'reload'}

Step 6: {'Step': '6. Replace or repair the faulty hardware (if necessary)', 'Action': 'replace or repair the faulty hardware component', 'Note': 'this step requires physical access to the switch and its components'}

Step 7: {'Step': '7. Verify the issue is resolved', 'Action': "run 'show alarm' command to confirm the alarm is cleared"}

Post-Check Verification

```
show alarm
show system resources
show environment
show power
show interface status
```